COMMON DRIVEWAY PLAN

69-71 BREWSTER ROAD

SUDBURY, MASSACHUSETTS

APRIL 24, 2017

REV: AUGUST 1, 2017 REV: SEPTEMBER 6, 2017 REV: SEPTEMBER 15, 2017 REV: JANUARY 11, 2018

REV: MARCH 2, 2018



SHEET 1 COVER SHEET


PLAN AND PROFILE SHEET 2 & 3

SHEET 4 - 6 GRADING AND DRAINAGE

> SHEET 7 STORMWATER POLLUTION

> > PREVENTION PLAN

SHEET 8 CONSTRUCTION DETAILS



LOCUS MAP SCALE: 1"=400'



AGUSTINA SUMITO, TRUSTEE LEEYA REALTY TRUST

REFERENCE


MIDDLESEX REGISTRY OF DEEDS SOUTH DISTRICT DEED BOOK 47283 PAGE 405

ZONING DISTRICT

RESIDENCE C

DATUM


N.A.V.D. OF 1988




LOCUS PLAN SCALE: 1"=1,200'


ENGINEER/SURVEYOR


STAMSKI AND MCNARY, INC. 1000 MAIN STREET ACTON, MASSACHUSETTS 01720




















FILTER CLOTH / MOUNTABLE BERM (OPT.) PAVEMENT <u>PROFILE</u> GROUND TO DRAIN PLAN VIEW STABILIZED CONSTRUCTION ENTRANCE

CONSTRUCTION SPECIFICATIONS

- 1. THE ENTRANCE OF THE PROPOSED DRIVEWAY SHALL INITIALLY HAVE 6" OF 2" CRUSHED STONE LAID DOWN AS A TRAFFIC SEDIMENT CONTROL SURFACE AS SHOWN IN THE STABILIZED CONSTRUCTION ENTRANCE DETAIL. THIS STONE PACK SHALL BE PLACED OVER THE DRIVEWAY FOR A MINIMUM DISTANCE OF 40 FEET FROM THE EDGE OF PAVEMENT AND SHALL BE REMOVED AND REPLACED WITH ROADWAY GRAVEL IMMEDIATELY PRIOR TO THE PLACEMENT OF PAVEMENT. 2. STONE SIZE — USE 2" CRUSHED STONE.
- 3. WIDTH TWENTY (20) FOOT MINIMUM, BUT NOT LESS THAN THE WIDTH AT POINTS OF INGRESS
- 4. FILTER CLOTH WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO THE PLACEMENT OF STONE.
- 5. SURFACE WATER ALL SURFACE WATER FLOWING OR DIVERTED NEAR CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED. 6. MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT
- TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMANDS AND REPAIR ANY MEASURES USED TO TRAP SEDIMENT,
- 7. WASHING WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO THE ENTRANCE ONTO PUBLIC RIGHT-OF-WAYS. WHEN WASHING IS DONE IT SHALL BE DONE ON STABILIZED ENTRANCE WITH STONE AND WHICH DRAINS INTO THE SEDIMENT SUMP AS SHOWN.
- 8. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN STORM.







EROSION CONTROL AND LANDSCAPE PLAN

EROSION CONTROL SEED MIX. ANY PLANT SPECIES USED ON SITE SHALL BE NATIVE TO MIDDLESEX

COUNTY OR CULTIVARS OF THESE NATIVE SPECIES. ANY MATURE TREES WITHIN LIMIT OR WORK SHALL BE PRESERVED WHERE

PLANTING NOTES

THE USE OF WILDFLOWER AND MEADOWS AND SHRUBS IS ENCOURAGED.

ALL SLOPES 3:1 OR GREATER SHALL BE SEEDED WITH NEW ENGLAND

SCALE: 1"=40'

EROSION AND SEDIMENTATION CONTROL NOTES

THE LIMIT OF WORK LINE SHALL BE CLEARLY MARKED IN THE FIELD BY FIELD SURVEY PRIOR TO CONSTRUCTION WITHIN DESIGNATED AREA. LIMIT OF WORK LINE SHALL NOT EXCEED THE LINE SHOWN, DEPICTED AS THE SILTATION BARRIER. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED FOR EACH PHASE PRIOR TO ANY CONSTRUCTION ON THE SITE. CONTRACTOR IS ENCOURAGED TO USE "FILTERMITT" IN LIEU OF STRAW BALE/SILTATION BARRIER.

DURING DEVELOPMENT AND CONSTRUCTION, ADEQUATE PROTECTIVE MEASURES SHALL BE PROVIDED TO MINIMIZE DAMAGE FROM SURFACE WATER TO THE CUT FACE OF

EXCAVATIONS OR THE SLOPING SURFACE OF FILLS. LAND SHALL BE DEVELOPED IN INCREMENTS OF WORKABLE SIZE WHICH CAN BE COMPLETED DURING A SINGLE CONSTRUCTION SEASON. EROSION AND SEDIMENT CONTROL

MEASURES SHALL BE COORDINATED WITH THE SEQUENCE OF GRADING, DEVELOPMENT, AND CONSTRUCTION, OPERATIONS. CONTROL MEASURES SUCH AS HYDROSEEDING, BERMS, INTERCEPTOR DITCHES, TERRACES, AND SEDIMENT TRAPS SHALL BE PUT INTO EFFECT PRIOR TO THE COMMENCEMENT OF EACH INCREMENT OF THE

THE CONTRACTOR SHALL INSPECT AND REPAIR ALL EROSION CONTROL DEVICES, WHEN INTENSE RAINFALL IS PREDICTED. THE CONTRACTOR'S REPRESENTATIVE SHALL INSPECT THE CONSTRUCTION SITE AT LEAST EVERY 7 DAYS AND WITHIN 24 HOURS OF A RAINFALL OF 0.5 INCHES OR MORE. AREAS WITH SITES THAT HAVE BEEN FINALLY STABILIZED MUST BE INSPECTED AT LEAST ONCE A MONTH.

STOCK PILES SHALL BE SET BACK A MINIMUM OF 5 FEET FROM THE EDGE OF PAVEMENT. ALL STOCK PILES SHALL BE CONTAINED WITH SILT FENCES OR STRAW BALES TO PREVENT EROSION FROM ENTERING THE STREET DRAINAGE. NPDES PERMITS REQUIRE THE STOCKPILES TO BE STABILIZED WITH SEED OR MULCH IF NOT BEING USED WITHIN 21 DAYS. SOIL STOCK PILES SHALL BE COVERED WITH TEMPORARY VEGETATION OR FASTENED WITH TARPAULIN SHEETS. STOCKPILES SHALL AVOID ALL SOIL ABSORPTION AREAS DURING CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN A ONE FOOT HIGH BY TWO FOOT WIDE EARTHEN BERM ALONG THE EDGES OF THE DRIVEWAY TO DIVERT RUNOFF TO SEDIMENT BASINS. STRAW BALES MAY BE UTILIZED TO DIVERT RUNOFF FROM THE DRIVEWAY LOW POINTS TO THE SEDIMENT BASIN DURING CONSTRUCTION UNTIL THE

SEDIMENT BASINS (DEBRIS, BASINS, DE-SILTING BASINS, OR SILT TRAPS) SHALL BE INSTALLED IN CONJUNCTION WITH THE INITIAL GRADING OPERATIONS AND MAINTAINED THROUGH THE DEVELOPMENT PROCESS TO REMOVE SEDIMENT FROM RUNOFF WATERS DRAINING FROM LAND UNDERGOING DEVELOPMENT. SEDIMENT BASINS SHALL BE

INSTALLED OUTSIDE OF INFILTRATION PORTION OF INFILTRATION BASINS AND PROPOSED SEPTIC LEACHING AREAS. THE DEVELOPER IS REQUIRED TO CLEAN UP ANY SAND, DIRT, OR DEBRIS WHICH ERODES FROM THE SITE ONTO ANY PUBLIC STREET OR PRIVATE PROPERTY, AND TO REMOVE SILT OR DEBRIS THAT ENTERS ANY EXISTING DRAINAGE SYSTEM INCLUDING CATCH BASIN SUMPS, PIPE LINES, MANHOLES AND DITCHES. ALL CUT AND FILL SLOPES SHALL BE IMMEDIATELY COVERED WITH 6" LOAM AND SEEDED DURING THE GROWING SEASON (MARCH THROUGH MAY AND AUGUST TO OCTOBER

15) OR COVERED WITH A HAY MULCH DURING THE NON-GROWING SEASON (NOVEMBER 1 TO APRIL 1 AND JUNE AND JULY). PERMANENT SEEDING MAY BE DONE IN PEAK SUMMER MONTHS WITH PROPER MULCHING AND WATERING. DISTURBED AREAS WHERE CONSTRUCTION HAS PERMANENTLY OR TEMPORARILY CEASED MUST BE STABILIZED WITHIN 14 DAYS OF THE LAST DISTURBANCE. AREAS WHICH

WILL BE REDISTURBED WITHIN 21 DAYS DO NOT HAVE TO BE STABILIZED. ADDITIONAL EROSION CONTROL MEASURES SHALL BE STOCK-PILED ON-SITE, INCLUDING BUT NOT LIMITED TO CRUSHED STONE, STRAW BALES, SILT FENCE AND EROSION

. THE SEDIMENT SHALL BE REMOVED BEHIND ALL STRAW BALES AND SILT FENCES IF DEPTH EXCEEDS 6". SEDIMENT SHALL BE REMOVED TO OUTSIDE THE BUFFER ZONE OF

THE WETLANDS WHERE APPLICABLE.

. THE EROSION CONTROL DEVICES SHALL BE MAINTAINED UNTIL ALL TRIBUTARY SURFACES ARE STABILIZED. I. REMOVAL OF EXISTING VEGETATION SHALL BE WITHIN THE CLEARING LIMIT OF WORK AREA. DEPICTED AS THE PROPOSED TREE LINE.

5. DISTURBED SOIL RESULTING FROM THE REMOVAL OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED WITHIN 30 DAYS OF REMOVAL 7. VELOCITY CHECK DAMS — STRAW BALES WILL BE USED AROUND THE CATCH BASINS ON THE PROPOSED ROAD TO PROTECT THEM FROM THE ERODING SOILS AND PROVIDE A CHECK DAM* TO SLOW THE RUNOFF DURING THE CONSTRUCTION. THE DEVELOPER SHALL PROVIDE VELOCITY CHECK DAMS* IN ALL UNPAVED STREET AREAS AT THE

INTERVALS INDICATED BELOW: GRADE OF ROAD LESS THAN 4%

50 FEET 4% TO 9% OVER 9%

OCITY CHECK DAMS* IN ALL UN-VEGETATED OR UNPAVED CHANNELS AT THE INTERVALS INDICATED BELOW: THE DEVELOPER SHALL PROVIDE VEL GRADE OF CHANNEL

INTERVALS BETWEEN CHECK DAMS 100 FEET LESS THAN 3% 3% TO 6% 50 FEET


*CHECK DAMS IN UNPAVED DRIVES AND UN-VEGETATED OR UNPAVED GRADED CHANNELS SHALL BE CONSTRUCTED OF STAKED STRAW BALES OR OTHER EROSION RESISTANT MATERIALS APPROVED BY THE BOARD. THE CHECK DAMS SHALL BE INSTALLED AT THE END OF EACH WORKING DAY, AND IN THE EVENT OF RAINFALL BEING PREDICTED. THE STRAW BALES SHOULD BE SECURELY STAKED TO PREVENT OVERTURNING, FLOATATION, OR DISPLACEMENT. THEY SHALL EXTEND COMPLETELY ACROSS THE STREET OR

CHANNEL AT RIGHT ANGLES TO THE CENTERLINE. ALSO, A VELOCITY CHECK DAM SHALL BE PROVIDED ALONG THE ENTRANCE OF THE LOT TO PROTECT THE PUBLIC STREETS AND ADJACENT PROPERTIES FROM THE HAZARDS OF EROSION. ALL CHECK DAMS SHALL BE CLEANED OF DEBRIS AND SILT PERIODICALLY. CONTRACTOR SHALL ROPE OFF AND FLAG PROPOSED INFILTRATION AREAS TO PREVENT HEAVY EQUIPMENT FROM COMPACTING UNDERLYING SOILS. DIVERSION BERMS SHALL BE PLACED AROUND PERIMETER OF INFILTRATION AREA DURING ALL PHASES OF CONSTRUCTION. SEDIMENT AND EROSION CONTROLS SHOULD BE USED TO KEEP RUNOFF AND SEDIMENT AWAY FROM INFILTRATION AREA. ALL EXCAVATED MATERIALS SHALL BE PLACED DOWN GRADIENT OF ALL INFILTRATION AREAS.

THE CONTRACTOR IS RESPONSIBLE TO CLEAN UP ANY SEDIMENT OR DEBRIS WHICH ERODES FROM THE SITE INTO THE WETLANDS IMMEDIATELY UPON DISCOVERY. 3. THE CONTRACTOR IS RESPONSIBLE TO CLEAN UP ANY SEDIMENT OR DEBRIS WHICH ERODES FROM THE SITE INTO BREWSTER ROAD OR PRIVATE PROPERTY AND TO REMOVE

SEDIMENT OR DEBRIS THAT ENTERS ANY EXISTING DRAINAGE SYSTEM INCLUDING CATCH BASIN SUMPS, PIPE LINES, MANHOLES, AND DITCHES. THE CONTRACTOR SHALL FOLLOW STANDARD PRACTICE AND LOAM AND SEED ALL DISTURBED AREAS FOLLOWING CONSTRUCTION. A MAINTENANCE AND OPERATION PLAN

SHALL BE IN PLACE AT ALL TIMES ON THE SITE. 20. OPERATOR PERSONNEL MUST INSPECT THE CONSTRUCTION SITE AT LEAST EVERY 7 DAYS AND WITHIN 24 HOURS OF RAINFALL OF 0.5 INCHES OR MORE. DISTURBED AREAS THAT HAVE BEEN STABILIZED MUST BE INSPECTED AT LEAST ONCE PER MONTH. 1. THE HAYBALES AND SILT FENCE SHALL BE MAINTAINED UNTIL A VEGETATIVE COVER HAS BEEN ESTABLISHED.



SILTATION BARRIER DETAIL

N.T.S.

STORMWATER OPERATION & MAINTENANCE PLAN

. BMP OWNER: YUCHUN LEE (DURING CONSTRUCTION) HOMEOWNERS (POST CONSTRUCTION)

2. PARTIES RESPONSIBLE FOR MAINTENANCE: OWNERS OF INDIVIDUAL LOTS ARE RESPONSIBLE FOR DRYWELLS AND TRENCHES LOT. BOTH HOMEOWNERS ARE RESPONSIBLE FOR THE COMMON DRIVEWAY AND ASSOCIATED DRAIN. 3. SCHEDULE FOR INSPECTION AND MAINTENANCE:

STREET SWEEPING:
IT IS RECOMMENDED THAT THE PAVEMENT SHALL BE PROPERLY SWEPT TWICE A YEAR, WITH CONCENTRATIONS IN THE SPRING AND FALL.

INFILTRATION TRENCHE INFILTRATION TRENCHES SHALL BE INSPECTED ANNUALLY. THE FILTER FABRIC SHALL BE INSPECTED FOR EXCESSIVE SEDIMENT

BUILD UP. IF APPRECIABLE AMOUNTS OF SEDIMENT ARE OBSERVED THE TOP LAYER OF STONE SHALL BE MOVED ASIDE AND THE FILTER FABRIC CLEANED OR REPLACED. THE TOP LAYER OF STONE SHALL THEN BE WASHED AND PLACED OVER THE

STONE DIAPHRAGM AND VEGETATIVE FILTER STRIP:
THE STONE DIAPHRAGM AND VEGETATIVE FILTER STRIP SHALL BE INSPECTED ANNUALLY. INSPECT THE CRUSHED STONE FOR SEDIMENT BUILDUP AND THE FILTER STRIP FOR STABLE VEGETATION. MOW GRASS, REMOVE SEDIMENT AND RESEED BARE **ROOF DRYWELLS:**

INSPECT DRYWELLS AFTER EVERY MAJOR STORM FOR THE FIRST FEW MONTHS TO ENSURE PROPER STABILIZATION AND FUNCTION. THEREAFTER, INSPECT AND CLEAN IT AT LEAST ONCE PER YEAR. WATER LEVELS SHOULD BE RECORDED OVER SEVERAL DAYS TO CHECK THE DRYWELL DRAINAGE.

DEEP SUMP AND HOODED CATCH BASIN: DURING CONSTRUCTION, CATCH BASIN GRATES SHALL BE WRAPPED IN FILTER FABRIC. CATCH BASINS SHALL BE CLEANED UPO THE COMPLETION OF CONSTRUCTION. AFTER CONSTRUCTION, THE DEEP SUMPS FOR ALL CATCH BASINS AND DRAIN MANHOLES SHALL BE INSPECTED AND CLEANED FOUR TIMES A YEAR. SEDIMENT REMOVED SHALL BE DISPOSED OF IN ACCORDANCE WITH

APPLICABLE LOCAL, STATE, AND FEDERAL GUIDELINES AND REGULATIONS. -THE DEPTH OF THE SEDIMENT IN A BASIN SHALL NOT EXCEED A DEPTH OF 18 INCHES AS DETERMINED BY PROBING WITH A STICK. IF THE STICK HITS THE BOTTOM WITHIN 30 INCHES OF THE WATER LEVEL, MORE THAN 18

INCHES HAS ACCUMULATED AND MUST BE REMOVED. LICENSED PERSONS SHOULD REMOVED AND DISPOSE OF THE


CONTENTS OF THE SUMP IN ACCORDANCE WITH APPLICABLE REGULATIONS.

IN THE EVENT OF A HAZARDOUS SPILL ON THE SITE THE FOLLOWING PARTIES SHALL BE CONTACTED:

FIRE DEPARTMENT: (978) 443-2239 **RECORDS:**

THE OWNER SHALL MAINTAIN AN INSPECTION LOG OF ALL ELEMENTS OF THE STORM WATER MANAGEMENT PLAN. THE OWNER SHALL MAINTAIN A MAINTENANCE LOG DOCUMENTING THE INSPECTION AND MAINTENANCE OF THE DRAINAGE STRUCTURES UNDER HIS CONTROL. A COPY OF THE EROSION CONTROL AND STORMWATER MAINTENANCE PLAN AND INSPECTION LOGS SHALL BE KEPT ONSITE AT ALL TIMES.

MEMBERS OF THE SUDBURY PLANNING BOARD OR ITS DESIGNEE SHALL BE ALLOWED TO ENTER THE PROPERTY AT REASONABLE TIMES AND IN A REASONABLE MANNER FOR THE PURPOSES OF INSPECTION, IN ACCORDANCE WITH THE TOWN'S STORMWATER REGULATIONS.



COMMON DRIVEWAY PLAN

69-71 BREWSTER ROAD SUDBURY, MA

STORMWATER POLLUTION PREVENTION PLAN


FOR: SCALE: NTS


APRIL 24, 2017 REV: AUG. 1, 2017; REV: SEPT. 6, 2017 REV: SEPT. 15, 2017; REV: JAN. 11, 2018 REV: MAR. 2, 2018


STAMSKI AND McNARY, INC. 1000 MAIN STREET ACTON, MASS.


ENGINEERING - PLANNING - SURVEYING


(5126B SITE.L.DWG) SM-5126B SHEET 7 OF 8


















LINE WITH 6" MIN. DIMENSION


FILTER FABRIC -


SIDE FLEVATION


PIPE END DETAIL


ADS N12





















-- LEVEL LIP OF SPREADER (SLOPE=0% ALONG


\ ENTIRE LENGTH)


-2' MIN.-

- UNDISTURBED

SOLID/VEGETATION








COMMON DRIVEWAY SWALE AND CHECKDAM

PROFILE NOT TO SCALE




3/4" DOUBLE WASHED


COMPACTED IN 6"


LIFTS TO AT LEAST


85% OF STANDARD

PROCTOR DENSITY











1 SLOPE





SHEET 8 OF 8





COMMON DRIVEWAY PLAN





(5126B SITE.L.DWG)

SM-5126B

